

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT9245/CALL-2

APPROVED SCHEDULE - B**Tender Notification No: No.EE/BTP/BBMP/E-PMT/16/2013-14, Date: 06.12.2013****Estimate for the Improvement of Roads and Drains from Gangamma Temple to Kodigehalli Main Road in ward No. 08 (Kodigehalli) Kodigehalli sub division.**

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				NAGALAPATI VENU	
				In Figures	In Words
1	225.6	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH chapter 3. No. 125/ Item No. 19.1/ PWD SR 2013-14	cum	65.22	Rupees Sixty Five and Twenty Two Paise Only
2	161	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for haulage and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 141 (SR 2013-14)	cum	77.46	Rupees Seventy Seven and Forty Six Paise Only
3	169.2	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2013-14	Cum	4247.93	Rupees Four Thousand Two Hundred Forty Seven and Ninety Three Paise Only
4	112.8	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Page No. 19/ Item No. 4.48/ PWD SR 2013-14	Cum	6400.23	Rupees Six Thousand Four Hundred and Twenty Three Paise Only

Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92